


ग्रामीण पाणी पुरवठा विभाग, जिल्हा परिषद सोलापूर
निविदा सुचना सन 2024-2025


कार्यकारी अभियंता, ग्रामीण पाणी पुरवठा विभाग, जिल्हा परिषद सोलापूर हे 15 वा वित्त आयोग जिल्हा परिषद स्तरावरील निधी मधुन मौजे धानोरे (सुरेश चव्हाण घराजवळ) तालुका माळशिरस गावामध्ये आर.ओ. फिल्टर बसविणे हे काम करणे आहे. अशा प्रकारच्या कामाचा अनुभव असणारे ठेकेदारांकडून निविदा मागविण्यात येत आहेत. कोऱ्या निविदा विक्री दिनांक :- 11/12/2024 रोजी सकाळी 10.00 वाजले पासून दिनांक :- 18/12/2024 रोजी दुपारी 18.00 वाजे पर्यंत यांत्रिकी उपविभाग, जिल्हा परिषद, सोलापूर येथे (शासकीय सुट्टी दिवस वगळुन) उपलब्ध राहिल.

निविदेचा तांत्रिक लिफाफा दिनांक :- 19/12/2024 रोजी उघडण्यात येईल.

अ. क्र.	कामाचे नांव	अंदाजपत्रकीय रक्कम रुपये	बयाणा रक्कम रुपये	कामपुर्ण करणेची मुदत	अधिकृत ठेकेदाराचा वर्ग
1	2	3	4	5	6
1	मौजे धानोरे तालुका माळशिरस, (सुरेश चव्हाण घराजवळ) येथील आर.ओ. फिल्टर बसविणे.	3,49,739/-	3,500/-	90 दिवस	अशा प्रकारच्या कामाचा अनुभव असणारे ठेकेदार

- उपरोक्त सर्व कामाबाबत निविदा, अटी व शर्ती इत्यादी बाबतचा सर्व तपशिल निविदा संचामध्ये नमुद केलेला असून कोऱ्या निविदा संच उप अभियंता (यांत्रिकी), यांत्रिकी उपविभाग, जिल्हा परिषद सोलापूर येथे मिळतील.
- उपरोक्त तक्त्यातील कामाचे नावासमोर रकाना क्र. 04 मध्ये नमुद केलेल्या बयाणा रक्कम धनाकृष मुख्य लेखा वित्त अधिकारी, जिल्हा परिषद सोलापूर च्या नावे तयार करुन सदर निविदेतील तांत्रिक लिफाफा कागदपत्रासोबत देणे.
- निविदेच्या अटी शर्ती बदल करणे, प्राप्त निविदापैकी, एक किंवा सर्व निविदा कोणतेही कारण न देता नाकारणेचा हक्क निम्न स्वाक्षरीत यांनी राखुन ठेवला आहे.


उप अभियंता (यांत्रिकी)
यांत्रिकी उपविभाग
जिल्हा परिषद सोलापूर


कार्यकारी अभियंता
ग्रामीण पाणी पुरवठा विभाग
जिल्हा परिषद सोलापूर

सविस्तर दरपत्रक सुचना

2024-25

1. सदर संपुर्ण निविदा प्रक्रिया निविदाद्वारे ऑफलाईन पध्दतीने आहे. सदर निविदेसंदर्भातील निविदा नोटीस प्रसिध्द, सुचना, शुध्दीपत्रके इत्यादीची माहिती www.zpsolapur.gov.in या संकेतस्थळावर उपलब्ध आहे.
2. निविदा सोबत खालील बाबी सादर करणे आवश्यक आहे.
(अ) सदर कामाची कोरी निविदा यांत्रिकी उपविभाग जिल्हा परिषद सोलापूर येथून रकाना क्र. 4 मध्ये नमुद रक्कमेचा राष्ट्रीयकृत बँकेचा धनाकर्ष / धनादेश जमा करण्यात यावे. संपुर्ण भरण्यात आलेले निविदा विहित वेळेत कार्यालयात जमा करावेत.
3. मक्तेदारांनी निविदा खालील प्रमाणे दोन लिफाफा (Two Envelope) मध्ये सादर करणे आवश्यक आहे.

(अ) तांत्रिक लिफाफा

1. निविदा फि रक्कम व निविदेची बयाना रक्कम जि.प.खाली भरणा केल्याच्या मुळ पावती (चलन)
2. शॉप अॅक्ट नोंदणी / उद्योग आधार नोंदणी प्रमाणपत्र / फर्म नोंदणी प्रमाणपत्र.
3. आर.ओ.फिल्टर बसविणे दोन योजना पुर्ण केलेले कामाचा अनुभव दाखला जोडणे.
4. पॅनकार्डची स्कॅन केलेली प्रत.
5. जी.एस.टी. प्रमाणपत्राची स्कॅन केलेली प्रत.
6. निविदा नोटीस मधील सर्व अटी व शर्ती मान्य असल्याचे हमीपत्र तसेच निविदे सोबत सादर केलेली सर्व माहिती व कागदपत्र खरी असल्याचे व ती संपुर्ण प्रक्रियेच्या (निविदा सादर करणे ते पेमेंट अदा करणे व त्या नंतर) कोणत्याही वेळी खोटी अथवा चुकीची आढळल्यास त्यास संबंधित ठेकेदार / कंत्राटदार स्वतः जबाबदार व कार्यवाईस पात्र राहतील अश्या आशयाचे प्रतिज्ञापत्र 100 रुपये च्या स्टॅम्पवर देणे.


(ब) अर्थिक लिफाफा


- ❖ मक्तेदारांनी आपले दर विहित ठिकाणी मध्ये योग्य त्या जागी भरून सदरची प्रत स्वतंत्र लिफाफा क्र. 2 मध्ये ठेवून लिफाफा बंद करावेत.
- ❖ लिफाफा क्र. 1 व लिफाफा क्र. 2 हे दोन्ही लिफाफा क्र. 3 मध्ये ठेवावेत.

दरपत्रकाच्या इतर अटी व शर्ती :

1. दरपत्रकाच्या किंमतीत अंदाजपत्रकानुसार साहित्य सर्व करांसहित पुरवठा करणे, उभारणी करणे, वाहतुक, पॅकींग व साहित्य गाडीत भरणे उत्तरविणे, कार्यान्वित करणे इत्यादी समावेश असेल.
2. निविदेतील सर्व साहित्य निविदेतील तांत्रिक निकषानुसार पुरवठा करावयाचे आहे. निविदेतील तांत्रिक निकषानुसार साहित्य नसल्यास ते स्विकारले जाणार नाही. सदरचे अधिकार उप अभियंता (यांत्रिकी) यांना असतील. सदर साहित्य नाकारले गेल्यास त्यांची जबाबदारी पुरवठाधारकाची राहिल.
3. सदर कामाचा पुरवठादार शक्यतो सोलापूर जिल्हयातील असावा अथवा पुरवठादाराचे सोलापूर जिल्हयामध्ये सेवा केंद्र (Service Center) असावे.
4. शासन निर्णय क्र. बीडीजी 2016 / प्र.क्र.2 / इमा 2 दिनांक :- 12/02/2016 अन्वये निविदा प्रक्रियेमध्ये प्राप्त निविदेचा देकार निविदाधिन कामाच्या किंमतीपेक्षा दहा टक्केयांपेक्षा आधिक दराने कमी असेल तर एवढ्या कमी दराने काम करण्याचे नियोजनाबाबत सविस्तर तपशिल सादर करण्यात यावा. तसेच निविदेचा देकार निविदाधिन कामाच्या किंमतीपेक्षा 10 टक्केयांपर्यंत

- कमी दराचा असेल तर ठेकेदरांनी निविदाधिन किंमतीच्या 1 टक्के एवढ्या रक्कमेचा धनाकर्ष / धनादेश परफॉर्मन्स सिक्युरिटी म्हणुन निविदेच्या लिफाफा देकार निविदाधिन कामाच्या किंमतीपेक्षा 10 टक्के पेक्षा जास्त दराने कमी असेल तर दराने 10 टक्के पेक्षा जेवढ्या दराने कमी आहे. तेवढ्या रक्कमेचा व वरीलप्रमाणे रक्कमेसह एकत्रित धनाकर्ष / धनादेश दराचा लिफाफा उघट्यावर आठ दिवसात कार्यालयास सादर करणे. (उदा. 14 टक्के कमी दर 10 टक्क्यांपर्यंत 1 टक्का व व 14) - 10 टक्के) - 4 टक्के असे एकूण 5 टक्के)
5. आवश्यक कागदपत्रे / प्रमाणपत्रे सादर करण्यास तांत्रिक अडचणी असल्यास त्याबाबत निविदा स्विकारणे अथवा नाकारणे बाबत अंतिम निर्णय मा. कार्यकारी अभियंता, ग्रामीण पाणी पुरवठा विभाग, जिल्हा परिषद सोलापूर यांचा राहिल.
 6. निविदा / दरमंजूरी झाल्याचे कळविले नंतर निविदा प्रक्रियेतील कमीत कमी मंजूर दरानुसार कामे करण्यास / पुरवठा करण्यास तयार असल्याचे संमतीपत्र, रुपये 500/- किंमतीच्या स्टॅम्प पेपरवर साहित्य पुरवठा तथा अनुषंगीक कामे करण्यास तयार असल्याबाबत जिल्हास्तरावर करारनामा करुन 7 दिवसाच्या आत दयावा लागेल.
 7. सदर काम करताना कोणतीही हानी झाल्यास / अपघात झाल्यास त्याची सर्वस्वी जबाबदारी कंत्राटदाराची राहिल.
 8. अंदाजपत्रकातील साहित्याची तांत्रिक तपासणी उपअभियंता (यां), यांत्रिकी उपविभाग, जिल्हा परिषद सोलापूर यांच्या कार्यालयाकडून करुन घेतल्या शिवाय योजनेच्या स्थळी साहित्य आस्थापित करण्यात येऊ नये.
 9. अ) पुरवठा आदेश मिळाले पासुन 2 महिन्याचे आत काम पुर्ण करणे आवश्यक आहे.
ब) जर कंत्राटदाराने विहित मुदतीत आदेशित काम पुर्ण केले नाही तर किंवा विलंबाचा संयुक्तीक खुलासा न केल्यास आदेशीत कामाच्या पैकी बाकी असलेल्या कामाच्या किंमतीच्या अर्धा टक्का प्रति आठवडा या दराने दंड वसूल करण्यात येईल. हा दंड जास्तीत जास्त 5 टक्के रक्कम व अतिरिक्त सुरक्षा रक्कम जप्त करण्यात येईल. त्यानंतर सदरच्या मक्तेदारांचे नांव काळ्या यादीत समाविष्ट करण्यात येईल. पुन्हा फेर निविदा करुन काम पुर्ण करण्यात येईल.
 10. देयकातुन सुरक्षा रक्कम, आयकर, जी.एस.टी. जिपसेस व इतर सर्व करांची शासकीय नियमानुसार वजावट करुन देयक अदा करण्यात येईल.
 11. मक्तेदारांनी कामाचे नकाशे, निविदेतील अटी व शर्तीनुसार Specifications कामाचे स्थळ मंजूर व साहित्याची उपलब्धता या सर्व बाबींचा अभ्यास करुन निविदा सादर कराव्यात.
 12. मक्तेदारांनी सादर केलेली निविदा व निविदेतील दर, लिफाफा क्रं. 2 उघडले नंतर 90 दिवसा पर्यंत वैध राहतील.
 13. निविदेतील सर्व वा कोणतीही अटी वा शर्ती पुर्ण न करणाऱ्या मक्तेदाराच्या निविदा व अर्धवट सादर केलेल्या निविदा अपात्र समजल्या जातील.
 14. कोणत्याही अटीवर (Conditional) आधारित दरपत्रके स्विकारल्या जाणार नाहीत अथवा स्विकारल्या तरी मंजूर केल्या जाणार नाहीत.
 15. निविदेच्या अटी व शर्ती मध्ये बदल करणे, प्राप्त निविदा पैकी एक किंवा सर्व निविदा कोणतेही कारण न देता रद्दचा हक्क निम्न स्वाक्षरीत यांनी राखून ठेवला आहे.
 16. संक्षिप्त निविदा सुचना व सविस्तर सुचना निविदा तंत्राचा एक भाग राहिल.
 17. कोणत्याही बाबीसाठी काही तंटा निर्माण झाल्यास त्याबाबत न्यायालयात जाता येणार नाही.


उप अभियंता (यांत्रिकी)
यांत्रिकी उपविभाग
जिल्हा परिषद सोलापूर


कार्यकारी अभियंता
ग्रामीण पाणी पुरवठा विभाग
जिल्हा परिषद सोलापूर

Rural Water Supply Division

Mechanical Sub-Division

Zilla Parishad Solapur

2023-24

ESTIMATE FOR 15 TH FINANCE COMMISSION - ZP LEVEL

NAME OF WORK :

**PROVIDING,SUPPLYING AND
COMMISSIONING OF REVERSE OSMOSIS
SYSTEM 250LPH PER HOUR CAPACITY
AND SHED INSTALATION**

VILLAGE : DHANORE

TALUKA : MALSHIRAS

LOCATION : Near Suresh Chavan House

DISTRICT: SOLAPUR

ESTIMATED COST RS. 349739.00

Zilla Parishad Solapur
Rural Water Supply Division
Office Of Dy.Engineer(Mech), Mechanical Sub Division.

NAME OF WORK : PROVIDING , SUPPLYING AND COMISSIONING OF REVERSE OSMOSIS SYSTEM 250 LITRE PER HOUR WITH SHED .

ESTIMATE

Name of Village
Location

DHANORE
Near Suresh Chavan House


Taluka
District

MALSHIRAS
SOLAPUR


Quantity	Unit	ITEM	Rate	Per	Amount
		ITEM NO. 1			
		Providing, supplying and commissioning of Reverse Osmosis System With Drinking Water Automatic Dispensing Unit and maintains Quality Test Certificate			
1	Nos	250 LPH REVERSE OSMOSIS system with water Dispensing Machine With ATM , ONE YEAR WARRANTY	170000.00	Nos	170000.00
		The work contains following Items			
		1) Design			
		1) Flow Rate-250 lit./hour			
		1) Source of water :-well water/Bore water /River water			
		1.Raw Water Tank			
		1. Quantity			01 Nos
		2. Moc			HDPE , IS:12701
		3. Capacity			500 Lit.
		4. Accessories			Water Auto Censor
		2.Raw Water Pump			
		1. Quantity			01 Nos.
		2. Make			Kirloskar /Crompton/CRI/ Lubi/ Shakti /Sharp
		3. Capacity			0.5 HP (0.75 KW)
		4. Head			30 Mtr.
		5. Discharge			1000 LPH
		6. Accessories			Auto Cut Solenoid Valve ¼ Inches AC.
		3. Pressure Sand Filter			
		1. Quantity			01 Nos
		2. Vessel			F.R.P.
		3. Vessel Size			8 X 44 Inch
		4. Type			Down Flow
		5. Type Of Media			Silica Sand Multi Grade
		6. Accessories			Multi Port Valve
		7. Make			Proton/Aster
		4. Active Carbon Filter			
		1. Quantity			01 Nos.
		2. Vessel			F.R.P
		3. Vessel Size			8 X 44 Inch
		4. Type			Down Flow
		5. Type Of Media			Activated Carbon (900 IV)
		6. Accessories			Multi Port Valve
		7. Make			Proton/Aster
		5. Micron Cartridge Filter			
		1. Quantity			01 Nos. (Big Jumbo)
		2. Cartridge			5 Micron
		3. Capacity			0.5 Cum/Hour
		4. Moc Of Cartridge			Polypropylene
		6. Antiscalent Dosing System			
		1. Quantity			01 Nos.
		2. Type			Electronic Dosing Pump
		3. Dosing Capacity			6 LPH
		4. Operating Pressure			2 Kg/sq.cm
		5. Make			Proton/ E Dose.
		6. Solution Tank			H.D.P.E.
		7. Tank Capacity			60 Lit.
		7. High Pressure Pump			
		1. Quantity			01 Nos.
		2. Power			1.5 HP
		3. Capacity			250 LPH
		4. Flow			1000 LPH
		5. Make			Crompton Greaves –Tera Flow/CRI/CNP/Leo/Lubi/ Shakti / Groundfos
		6. Accessories			With Low Pressure Switch.
		8. Chasis			
		1. Moc Of Chasis			S.S. Grid Chassis.

Quantity	Unit	ITEM	Rate	Per	Amount	
		9. Membranes				
		1. Quantity			Fully Machined	
		2. Mack Of Vessel			01 Nos.	
		3. Type Of Membrane			Stainles Steel	
		4. Membrane			Spirally Wounded	
		5. Housing			40-40 X 1 Nos.	
		5. Capacity			40 X 40 – 1 Nos.	
		6. Make			250 Lit/Hour	
		7. Accessories			Adwyn Chemicals/DOW/ Hydronotics	
		10. Instrumentation And Electrical Components			Necessary size of Module And pressure Tube, Auto Flush with 1/2 Inches Solenoid Valve.	
		1. Type			Fully Automatic	
		2. Accessories			1. Pressure Gauge-2 Nos	
					2. Rotameter- 600 – 1 Nos.	
					600 – 1 Nos.	
					3. Electronic Control Panel Board	
		11. Piping.			uPVC	
		1. Raw Water Tank To Inlet Of High Pressure Pump			S.S.-304 Stainles Steel Piping.	
		2. Out Let Of High Pressure Pump To Storage Tank				
		12. UV Disinfection Unit				
		1. Quantity			01 Nos.	
		2. Water Flow Rate			250 LPH	
		3. Type			Fluorescent Tube	
		4. Make			Philips / Aquvatic / Sukrut	
		13. Pure Water Storage Tank				
		1. Quantity			01 Nos	
		2. Type			Vertical	
		3. Capacity			500 Lit.	
		4. Moc Of Tank			S.S.-304 Stainles Steel	
		14. Dispense Unit (ATM)				
		1. Quantity			01 Nos.	
		2. Type			Multi Coin (Rs.1 & 5)	
		3. Moc of Dispense			Metal Body And Stainles Steel valves.	
		4. Make			Aster / Proton / etc	
		(As Per Rates Sanctioned By E.E. RWS , Z.P.Solapur on 01 /10/2020)				
		ITEM NO.02				
1	Nos	Chiller Of 1 Tonn Capacity , Chilling Range Minimum Water Temp 12C Discharge of Water 200 to 250 Ltrs/Hour (Compressor Make - Emerson / Kirloskar)				
		(As Per Rates Sanctioned By E.E. RWS , Z.P.Solapur on 01 /10/2020)				49000.00 Nos 49000.00
		ITEM NO.03				
1	Nos	Providing Fixing, Erecting Steel Fabricated Shed For Reverse Osmosis System				
		(As Per Rate Analysis)				129928.49 Nos 129928.49
		ITEM NO.04				
0.54	SqM	Material & labour for painting of matter given by dept. in diff. colour as per R.C (1.2 X 0.9)				
		Rates Aproved By GSDA /SOLAR PUMP /RC /F- NO 25/834/2013-14 dt 1.3.2014				1500.00 SqM 810.00
					TOTAL	349738.49
					TOTAL RS	349739.00

Estimate Prepared By



J.A. Engineer (Mech)
 Mechanical Sub Division
 Zilla Parishad Solapur


Checked And Submitted By


Dy. Engineer (Mech)
 Mechanical Sub Division
 Zilla Parishad Solapur

Zilla Parishad Solapur
Rural Water Supply Division
Office Of Dy.Engineer(Mech), Mechanical Sub Division.
Rate Analysis For Item No.2 Providing & Erecting Shed for 250 LPH Reverse Osmosis System.

Items	Qty.	Rate	Per	Amt.
Item No. 1 Excavation for foundation in earth soils of all types sand gravel and soft murum including removing the excavated material up to a distance of 50 M beyond the building area and stacking and spreading as directed as directed dewatering preparing the bed for foundation and necessary back filling ramming watering including shoring and strutting etc complete lift up to 1.50M(Mechanical Means)	1.82	239.00	Cum	435.58
(PWD.D.S.R. 2022-2023 Item No.12.02				
Item No. 2 Providing and laying in situ cement concrete in M.10 of trap metal for foundation and bedding including bailing outwait formwork compacting and curing with natural sand etc complete.	1.10	5830.00	Cum	6427.58
(P.W.D.S.R. 2022-23 Item No.24.01				
Item No. 3 Providing uncoursed rubble masonry of trap / granite / quartzite / gneiss stones in cement mortar 1:6 in foundation and plinth of inner walls / in plinth of external walls including bailing out water manually, striking joints on unexposed faces and watering etc complete	2.43	5025.00	Cum	12210.75
PWD DSR 2022-23 Item No.27.07				
Item No. 4 Filling in plinth and floors / trenches with contractor's murum for bedding in 15 cm to 20 cm layers including watering and compaction, etc. complete. (Bd-A-11/263)	2.02	912.00	Cum	1838.59
MJP DSR 2023-24 Item No.E-17				
Item No. 5 Providing and fabricating structural steel work enrolled sections like joints channel s angles ,tees etc as per detailed design and drawings including fixing in position without connecting plates, braces,etc and one coat of anti corrosive paint and over it two coats of oil painting of approved quality and shade etc .	0.245	101844.00	MT	24911.76
PWD DSR 2022-23 Item No.23.01				
Item No. 6 Providing and fixing plane zinc sheeting of 0.80 mm thick (22BWG) over the ridge hip or valley to galvanized iron sheet roofing including all fastening and boit, galvanized iron screw and bolt and lead and bitumen washers complete(Wt 6.8kg/sqm)	49.32	1139.00	Sq.M	56178.33
PWD DSR 2022-23 Item No.38.05				
Item No. 7 Providing and fixing on walls/ceiling/floor 25 mm dia. uPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	10.00	355.00	Mtr	3550.00
PWD DSR 2022-23 Item No.42.91				
ITEM NO.8 Electrification For Shed (As Per Rate Analysis)	1.00	3876.00	Job	3876.00
ITEM NO.9 Providing and laying Rough Shahabad Stone Flooring 25mm to 30mm thick and of required width in plain/ diamond pattern on a bed of 1:6 C.M. including cement float, striking joints, pointing in cement mortar 1:3 curing and cleaning etc. complete.	9.00	731.00	Sqm	6579.00
(PWD DSR 2022-23 I.No.33.01 Sr.No.981)				
			TOTAL	116007.58
			Add GST 12%	13920.91
			Gross Total	129928.49
			Say Rs.	129928


Junior Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur


Dy. Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur

Zilla Parishad Solapur
Rural Water Supply Division
Office Of Dy.Engineer(Mech), Mechanical Sub Division.
Rate Analysis For Electrification For Steel Fabricated Shed.

Qty	Unit	Description	Ref CSR 23-24	Rate	Amount
2	No.	Point wiring	1.7.16	411.00	822.00
2	No.	Plug Point	1.7.13	133.00	266.00
1	No.	DP MCB 16 AMP	5.3.7	535.00	535.00
12	Mtr	2x2.5sqmm copper conductor unarmoured cable	7.2.1	46.00	552.00
1	Nos	fresh air cum exhaust fan	2.9.13	1701.00	1701.00
Total Rs					3876.00


Junior Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur


Dy. Engineer (Mech)
Mechanical Sub Division
Zilla Parishad Solapur


Zilla Parishad Solapur
Rural Water Supply Division
Office Of Dy.Engineer(Mech), Mechanical Sub Division.
Name of Work-Providing & Erecting Shed for 250 LPH Water A.T.M.Machine etc


Measurement sheet

Items	No	Length	Breadth	Depth	Qty.	Unit
Item No. 1						
Excavation for foundation in earth soils of all types sand gravel and soft murum including removing the excavated material up to a distance of 50 M beyond the building area and stacking and spreading as directed as directed dewatering preparing the bed for foundation and necessary back filling ramming watering including shoring and strutting etc complete lift up to 1.50M(Mechanical Means)						
	2.00	3.30	0.45	0.45	1.34	
	1.00	2.40	0.45	0.45	0.49	
					TOTAL	1.82
Item No. 2						
Providing and laying in situ cement concrete in M.10 of trap metal for foundation and bedding including bailing outwait formwork compacting and curing with natural sand etc complete.						
For Angles	5.00	0.30	0.30	0.45	0.203	
For Flooring PCC	1.00	3.00	3.00	0.10	0.900	
					TOTAL	1.10
Item No. 3						
Providing uncoursed rubble masonry of trap / granite / quartzite / gneiss stones in cement mortar 1:6 in foundation and plinth of inner walls / in plinth of external walls including bailing out water manually, striking joints on unexposed faces and watering etc.complete						
For Wall	2.00	3.30	0.45	0.60	1.78	
For Wall	1.00	2.40	0.45	0.60	0.65	
					TOTAL	2.43
Item No. 4						
Filling in plinth and floors / trenches with contractor's murum for bedding in 15 cm to 20 cm layers including watering and compaction, etc. complete. (Bd-A-11/263)						
	1.00	2.40	2.40	0.35	2.02	
					TOTAL	2.02
Item No. 5						
Providing and fabricating structural steel work enrolled sections like joints channel s angles ,tees etc as per detailed design and drawings including fixing in position without connecting plates, braces,etc and one coat of anti corrosive paint and over it two coats of oil painting of approved quality and shade etc .						
M.S.Sq.Pipe 50x50x2.6mm						
Vertical Pipes	5.00	3.50	-	-	17.50	
Perling pipe Top side	9.00	3.30	-	-	29.70	
harizantal Pipes Wall No.01 , 02 and 03	3.00	3.30	-	-	9.90	
harizantal Pipes Wall No. 04	2.00	1.50	-	-	3.00	
					Total	60.10 RMT
		60.10	4.07	Kg/mtr	244.61	KG
		244.61	1000.00		0.245	MT
Item No. 6						
Providing and fixing plane zinc sheeting of 0.80 mm thick (22BWG) over the ridge hip or valley to galvanized iron sheet roofing including all fastening and bolt, galvanized iron screw and bolt and lead and bitumen washers complete(Wt 6.8kg/sqm)						

Items	No	Length	Breadth	Depth	Qty.	Unit
	4.00	3.00	-	3.00	36.00	
	1.00	3.65	3.65		13.32	
Total					49.32	
Deduction of Steel Rolling Shuter	0.00	1.50	3.00		0.00	
	Total Deduction				0.00	M3
					49.32	
Item No. 7						
Providing and laying in trenches 25 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.					12.00	
ITEM NO.8						
Electrification For Shed						
	1.00				1.00	Job


ITEM NO.9						
Providing and laying Rough Shahabad Stone Flooring 25mm to 30mm thick and of required width in plain/ diamond pattern on a bed of 1:6 C.M. including cement float, striking joints, pointing in cement mortar 1:3 curing and cleaning etc. complete.	MTR		MTR		TOTAL	
	3.00	x	3.00	=	9.00	Sqm
				=	0.00	Sqm
	SAY				=	9.00


 Junior Engineer (Mech)
 Mechanical Sub Division
 Zilla Parishad Solapur



 Dy. Engineer (Mech)
 Mechanical Sub Division
 Zilla Parishad Solapur

Information Board And Painting Mesurments

Sr No	Description	QTY	Length Mtr	Brudth	Total Mtrs	Kgs Per Mtr	Total Kgs
1	Information board of scheme- Providing structural steel work in trusses, other similar trussed purlins & members with all bracing, gusset plates, etc. as per detailed design & drawing or as directed by Engineer in charge including cutting, fabricating, Grouting and Fitting Work						
1.1	Name Board Vertical Angle Size 40mm x 40mm x 6mm Thick	2	2.1	-	4.2	3.5	14.7
1.2	Name Board Horizontal Angle Size 40mm x 40mm x 6mm Thick	2	1.2	-	2.4	3.5	8.4
1.3	M.S.sheet 1 mm thick (Wt. @ 7.85kg /sq.mtr)	1	1.2	0.9	1.08	7.85	8.478
						Total Kgs	31.578
2	Material & labour for Vinayl Painting of matter given by department on board by using diff. colours all as directed by Engineer - in - charge (As per Market Rate)	1	1.2	0.9	1.08	sq mtr	


Jr Engineer (Mech)
Mechanical Sub Division
Parishad, Solapur

Zilla


Dy Engineer (Mech)
Mechanical Sub Division
Zilla Parishad, Solapur

- वाचा :- 1) जिल्हा परिषद व पंचायत समिती लेखा संहिता 1968 मधील नियम क्र.4 चे परिशिष्ट 2
2) महाराष्ट्र शासन, शासन निर्णय क्र. झेडपीए2012/प्र.क्र.680/वित्त-09.दिनांक.31.01.2018
3) मा.मुख्य कार्यकारी अधिकारी यांचेकडील प्रशा.मान्यता आदेश क्र.275 दि.31/03/2022..

जा.क्र.उपअभि(यां)/यांउपवि/जिपसो/तांमा/ ^E700/2024.

उपअभियंता(यांत्रिकी),
यांत्रिकी उपविभाग,जिल्हा परिषद,
सोलापुर
दिनांक:- 09/07/2024

तांत्रिक मान्यता आदेश

उपरोक्त संदर्भीय क्र.01 चे अधिकार व संदर्भ क्र.02 च्या शासन निर्णयान्वये शासनाने प्रदान केलेल्या शक्तीचा उपयोग करुन मी, उपअभियंता(यांत्रिकी), यांत्रिकी उपविभाग, जिल्हा परिषद, सोलापुर खालील प्रमाणे प्रस्तावित कामास तांत्रिक मान्यता प्रदान करत आहे.

अ क्र	गाव / तालुका / ठिकाण		कामाचे विवरण	योजना	संख्या	अंदापत्रकीय खर्चाची रक्कम रुपये
1	गाव	धानोरे	आर ओ प्रकल्प उभारणी करणे	१५ वा वित्त आयोग - जि.प.स्तर	01	349739.00
	तालुका	माळशिरस				
	ठिकाण	सुरेश चव्हाण यांचे घराजवळ				
एकुण :-					349739.00	

(अक्षरी रक्कम रूपये तीन लाख एकोणपन्नास हजार सातशे एकुणचाळीस फक्त)


उपअभियंता (यांत्रिकी)
यांत्रिकी उपविभाग,जिल्हा परिषद,
सोलापुर

प्रती,
सरपंच / ग्रामसेवक,
ग्रामपंचायत कार्यालय, धानोरे , तालुका माळशिरस.
प्रत,
गट विकास अधिकारी,पंचायत समिती, माळशिरस यांना माहीतीस्तव सविनय सादर.